

Charlottesville Albemarle Airport

Invitation to Bid

Multi-Tasking Snow Removal Unit (MTE)

Include Carrier Vehicle with 22' Snow Plow, 20' Rotary Broom and High Velocity Air Blast System

ADDENDUM # 1

June 22, 2015

Page 16, Dimensions and Clearances, specifications of height of vehicle include lights and exhaust stacks shall be 132 inches. Height may be increased to 148 inches.

Page 34, Moldboard Assembly, plow width shall be 22". Pages 3,4,5 indicate plow width as 22' feet which is correct.

Page 37, Swept Path, Specification indicates 14.7 at 35 degrees. Correction, broom to be 20' 30 degree angle swept path 17.32.feet, 35 degree angle swept path 16.38 feet.

Page 37, Bristle Materials, bristle materials to be a polypropylene steel mix. Fifty percent polypropylene and fifty percent steel wire bristles.



**William D. Pahuta
Deputy Executive Director**